

An Energy Efficiency Workshop & Exposition

Kansas City, Missouri

Keeping it Going

W. Mark Arney, P.E., CEM

Architectural Energy Corporation

Steven Dorer

U.S. EPA



Outline of Today's Presentation

- Concepts of persistence and continuous commissioning
- Preventative and predictive maintenance
- Hardware and software tools
- Diagnostic Examples
- Applications at Pantex and the Ann Arbor EPA Lab



 The degradation of energy savings over time resulting from loss in measure efficiency or effectiveness, or from disabling the measure or reverting to the original technology.



Medical Analogy for Buildings

- Use diagnostics to identify problems
- Develop plan to fix problems
- Implement corrective procedures
- Continue to monitor systems for reoccurrence of problems



Continuous Commissioning

- A process for maintaining persistence
- Don't just commission a building once and then you are done
- Make it a cornerstone of an overall O&M program



Hand logs

- May seem outdated, but hand logs can be very useful.
- No substitute for experienced eyes and ears
- Preventative Maintenance
 - Regular maintenance at preset intervals
 - Many canned and customized software packages available



Predictive Maintenance

- Alternative to some preventative maintenance procedures
- Used to determine when a component is about to fail instead of just changing it because "it's time"
- Examples: vibration analysis, oil analysis, infrared thermography, ultrasonic noise detection.



Diagnostic Tools - Hardware

- Hand held devices for spot measurements
- Portable data loggers
- Permanent data loggers



- Power meter
- Temperature gages
- Manometers
- Flowhoods



Hand Held Wattmeter

- amps
- > volts
- > true RMS power
- power factor
- crest factor
- wave form





Portable Data Loggers

- Gather information on setpoints, schedules, loadshapes, etc
- Short term diagnostic testing
 - Observe dynamic performance changes as opposed to static conditions.
 - Observe system operation in their "natural" operating modes.
- Software provides semi-automated diagnostics, data visualization, advanced filtering.
 June 3-6, 2001



Portable, Battery-Powered Data Logger








 Installation of data logger in a motor control center




Example Diagnostic Plot #1

Simultaneous Heating and Cooling






Example Diagnostic Plot #2 - Duct Heaters





Example Diagnostic Plot #3 Electric Defrost Circuits



June 3-6, 2001

www. energy2001.ee.doe.gov



Permanent data loggers

- Used to verify long term performance
- EMCS now capable of this task
- Lots of data to analyze



New Wireless Monitoring Technology


- Wireless system is Internet accessible
- Sensors transmit to receiver located in a nearby PC
- Capable of limited control, not just monitoring
 - demand limiting
 - > others



Wireless Watt Transducer









Diagnostic Tools - Software

- Computer simulation
- Data analysis / diagnostics programs
- Spreadsheets



Data analysis / diagnostics programs

- ENFORMA
- PACRAT
- Universal Translator
- Whole Building Diagnostician




Using the EMCS for diagnostics

- Now have more capability for data collection and analysis (speed & memory)
- On-line diagnostics
 - making sense out of trend logs
- Submetering Applications
 - billing
 - diagnostics



EMCS Trend Logs

Exhaust Fan 6: % Speed





Problem at Pantex

- No funding for the Low Cost portion of the Low Cost / No Cost Program
- No funding for the \$1,000,000 effort for Construction Support agreed to in the ESPC contract
- No funding for the contractually obligated manufacturer recommended maintenance on ESPC installed equipment
- Guaranteed Savings portion of contract negated if this isn't performed!



Solution for Pantex

- Establish a site-wide Continuous Commissioning Program on HVAC systems
- Generate enough savings to pay for the ongoing commissioning program
- AND enough savings to pay for the ESPC construction and maintenance effort



Commissioning Program Goals

- Engage commissioning firm to develop a Continuous Commissioning Plan for Pantex
- Train energy manager in procedures of commissioning and the use of hardware and software for operational diagnostics
- Establish templates to document the planning, investigation, implementation, and results of commissioning effort



Commissioning Program Goals

- Achieve energy savings through low cost no cost improvements to existing mechanical systems
- Provide documentation of savings to assist the Pantex energy manager in planning expenditures within the utility procurement budget
- Provide sufficient documented energy savings to fund the required operations and maintenance requirements associated with the ESPC
- Satisfy the operational needs of the occupants of each selected facility



Commissioning Program Methodology

- Short-term Diagnostic Monitoring
- Use hardware and software tools specifically oriented towards operational diagnostics
- Dedicated software manages, calculates and filters the data, then provides diagnostic plots to analyze system performance
- Investigates dynamic interactions between components and systems
- Provides information for diagnostics and M&V baseline



Pantex - Conclusions

- Diagnostic tools (hardware and software) are effective and efficient commissioning tools
- Consistent methodology for data collection and analysis
- Simultaneously provide diagnostics and energy information
- Initial results show potential energy savings
- Program meets objectives in very challenging work environment (financial, security, labor)



Keeping it Going in Ann Arbor

- Project Goals
 - Save Energy
 - Comply with Energy Policy Act
 - Comply with Exec. Order 12902
 - Restore aging, energy inefficient building infrastructure



EPA's NVFEL in Ann Arbor





What Did We Get?

- EPA's First ESPC
- 37 Roof Top Air Handlers
- Two Natural Gas Chiller/Heaters
- 200 kW Natural Gas Fuel Cell
- \$10.6M Upgrade Without Up Front Funding



What Do We Expect?

- 50% Less Energy Consumption
- Lower Utility Plant Emissions
- Lower Site Emissions
- To Serve as an Example to Other Public and Private Sector Facilities



- New Air Handlers
- New central plant
- New EMCS



Chiller / Heater





New Air Handling Units





200 kW Fuel Cell





Tools Used at Ann Arbor

- Baselining and ECM Identification
 - Short tem diagnostic testing
 - Calibrated building energy model
- Post Retrofit Tools
 - Detailed M&V using the EMCS
 - System Diagnostics using the EMCS




Justification for Obtaining Tools

- Needed for ESPC
- Detailed M&V plan required some sophisticated tools
- Costs are rolled into ESPC payments




Fuel Cell Energy Accounting





M&V Accounting by AHU





System Diagnostic Summary

- Original concept was whole building COP
- Modified concept to system and component level diagnostics
- Focus on Test Cell AHUs and central plant
- Set alarm flags for non-optimal performance



System diagnostics equations



Key persistence issue - control of test cells

- Honor system with enforcement
- Has been a culture change
- Proposed parking ticket approach
- Avoid using computer for AHU shutdown



THANK YOU

- For more information contact:
- Mark Arney, P.E.
- Architectural Energy Corporation
- (303) 444-4149
- marney@archenergy.com
- www.archenergy.com

- Steven Dorer
- National Vehicle Fuel Emissions Laboratory
- o (734) 214-4503
- DORER.STEVEN@epamail.epa.gov